ConvexHire

Final Year Project Report

Student Name: Rahul Dev Banjara
University ID: 2407061
Supervisor: Ms. Prakriti Regmi
Reader: Mr. Siman Giri
Module: Final Year Project

Academic Year 2025 / 2026

Table of Contents

Acknowledgements ..... **v**
Abstract **1**
1 Introduction **2**
1.1 Project Briefing (humanized) 2
1.1.1 AI Aspect (humanized) 2
1.2 Academic Question 4
1.3 Aims (humanized) 4
1.4 Objectives (humanized) 4
1.5 Artefact 5
1.5.1 FDD 5
1.6 Scope and Limitations (humanized) 5
1.6.1 Scope 5
1.6.2 Limitations 6
1.7 Report Structure 6
2 Literature Review **7**
2.1 AI in Talent Acquisition and Automated Screening (humanized) 7
2.2 Resume Analysis, Semantic Matching, and Hybrid Retrieval 8
2.3 Multi-Agent and Multi-Persona LLM Architectures 8
2.4 Cost-Efficient AI Pipelines 8
2.5 Security and Privacy in AI Pipelines 9
2.6 Multilingual and Low-Resource Speech Recognition 9
2.7 Human-in-the-Loop AI for Consequential Decisions 9
2.8 Similar Systems 10
2.8.1 Nepal-Based Systems 10
2.8.2 Commercial Platforms 10
2.8.3 Research Prototypes 10
2.9 Gap Analysis 11
3 Project Methodology **12**
3.1 Framework Justification (Kanban) 12
3.2 High-level Gantt Chart 12
4 Tools and Technologies **13**
5 Artefact Designs **14**
5.1 Subsystem 1 Authentication, User Management and Company Management (humanized) 14
5.2 Subsystem 2 Machine Learning based and Multi Agent Shortlisting (humanized) 16
5.3 Subsystem 3 Recruiter Chatbot with Agentic RAG (humanized) 21
5.4 Subsystem 4 AI Resume Parsing and Job Fit Gap Analysis (humanized) . 23
5.5 Subsystem 5 Fine-Tuned ASR for Interview Transcription and Scoring (humanized) 26
5.6 Subsystem 6 AI Job Drafting and Hybrid Semantic Search (humanized) . 29
5.7 Subsystem 7 AI Outreach Drafting and Interview Scheduling (humanized) 32
5.8 Entity-Relationship Diagram (humanized) 35
5.9 Finetuning OpenAI Whisper (humanized) 35

5.9.1 Integration (humanized) 36
6 Test Plans 37
6.1 Introduction 37
6.2 Traditional Software Testing (Deterministic) 37
6.2.1 Integration Testing 37
6.2.2 ML Prefilter Classification 37
6.3 AI Intelligence Benchmarking (Probabilistic) 38
6.3.1 R&D Benchmark OCR and Layout Parsing (humanized) 38
6.3.2 Hybrid Search Ranking Evaluation 39
6.3.3 ASR Performance Whisper Fine-Tuning 39
6.4 Guardrails (humanized) 39
6.4.1 Input Guardrail Prompt Injection Defense (humanized) 40
6.4.2 Content Guardrail PII Redaction and Bias Mitigation 40
6.4.3 Output Guardrail Hallucination Prevention 40
7 Conclusion 42
8 Critical Evaluation 43
8.1 Final Report Reflection 43
8.2 Findings and System Evaluation 43
8.3 System Evaluation 43
8.4 Self-Reflection and Professional Development 44
9 Evidence of Project Management 46
9.1 Log Sheets 46
9.2 Gantt Chart 46
9.3 Trello Board 46
References 47
10 Appendices 49
10.1 Wireframes 49
10.2 Additional Diagrams 49

List of Figures

Figure 1 Feature Decomposition Diagram of ConvexHire 5
Figure 2 High-level Gantt Chart 12
Figure 3 Authentication, User and Company Management activity diagram 15
Figure 4 Authentication, User and Company Management class diagram 16
Figure 5 Authentication, User and Company Management sequence diagram 16
Figure 6 ML and multi-agent shortlisting activity diagram 18
Figure 7 ML and multi-agent shortlisting class diagram 19
Figure 8 ML and multi-agent shortlisting sequence diagram 20
Figure 9 Compiled LangGraph workflow for the multi-agent shortlisting pipeline 20
Figure 10 Recruiter chatbot with agentic RAG activity diagram 21
Figure 11 Recruiter chatbot with agentic RAG class diagram 22
Figure 12 Recruiter chatbot with agentic RAG sequence diagram 23
Figure 13 AI resume parsing and job-fit gap analysis activity diagram . 24
Figure 14 AI resume parsing and job-fit gap analysis class diagram 25
Figure 15 AI resume parsing and job-fit gap analysis sequence diagram 26
Figure 16 Fine-tuned ASR for interview transcription and scoring activity diagram 27
Figure 17 Fine-tuned ASR for interview transcription and scoring class diagram 28
Figure 18 Fine-tuned ASR for interview transcription and scoring sequence diagram 29
Figure 19 AI job drafting and hybrid semantic search activity diagram . 30
Figure 20 AI job drafting and hybrid semantic search class diagram ... 31
Figure 21 AI job drafting and hybrid semantic search sequence diagram 32
Figure 22 AI outreach drafting and interview scheduling activity diagram 33
Figure 23 AI outreach drafting and interview scheduling class diagram . 34
Figure 24 AI outreach drafting and interview scheduling sequence diagram 34
Figure 25 Conceptual entity-relationship diagram of ConvexHire 35
Figure 26 Training curves - train and validation loss, WER, CER, and cosine learning rate schedule across all training steps 36
Figure 27 Confusion matrix of the RandomForest ML bouncer 37
Figure 28 Global feature importance of the RandomForest ML bouncer 38
Figure 29 Detailed Gantt chart for the development lifecycle 46
Figure 30 Kanban board on Trello 46
Figure 31 Candidate dashboard wireframe 49

List of Tables

Table 1 Technology stack overview 13
Table 2 OCR and layout parsing comparative analysis 38
Table 3 Hybrid search eval, 7 of 7 queries returned the expected job at rank 1 39
Table 4 Whisper Small fine-tuning results on the Nepali validation set (lower is better) 39
Table 5 NeMo Guardrails test results 40

Acknowledgements

I would like to express my sincere gratitude to my supervisor for the steady guidance, honest feedback, and patience throughout every stage of this project, from the initial scoping discussions to the final review of the artefact and the report.

I am grateful to the module leaders and the wider faculty at Herald College Kathmandu and the affiliated programme at University of Wolverhamtpon for setting the academic framework within which this work was carried out, and for the support and resources made available during the year.

I would like to thank the recruiters and candidates who took time out of their own work to walk through early prototypes, share their real hiring pain points, and give the kind of frank feedback that no amount of desk research could have produced. Their input shaped many of the design choices documented in this report.

I am thankful to my fellow students for the technical discussions, the second opinions when I was stuck, and the moral support during the long stretches of the project where progress felt slow.

Abstract

(humanized)

ConvexHire is an AI-powered recruitment platform that aims to simplify the entire recruitment journey for job seekers and employers. For candidates, it enables them to upload their CV to AI, create their profile, and even receive an evaluation of the weaknesses in their CVs in relation to a job description and their ability to improve it. They can also find relevant jobs with a hybrid search (semantic plus keywords). The platform automates writing job descriptions, rates candidates and also performs intelligent shortlisting for recruiters. There is also an AI assistant which can search talent and find salary data. The recordings from the interviews are transcribed with a finetuned Whisper model for Nepali language. All actions generated with AI, whether it is an outreach email, or any modification, must be approved by a human (HITL) before it is performed, ensuring that the recruiter always have the control. It also logs applications in real-time with AI scores and feedback for both parties, and provides suitable guardrails to ensure a fair and efficient pipeline. The system's tag line is "AI should assist, not replace human decision-making.

1 Introduction

1.1 Project Briefing (humanized)

ConvexHire is an AI-augmented recruitment platform that automates and enhances the full hiring lifecycle for both job seekers and recruiters. The system integrates AI-driven tools to draft job descriptions, existing resume imports, job matching according to skills, and preferences, and assistant recruiter to shortlist. ConvexHire is built on a Human-in-the-Loop (HITL) architecture which means every decision made by AI has to be approved by a human before finally it takes place. The system has three user roles: candidates, recruiters, and company administrators. For candidates, the system makes easier to find the appropraite job they want to apply to, along with maximizing their chance of shortlist (if they are a good fit), by allowing them to find any gaps in their selected resume by comparing against the job description. For recruiters, the system provides with different smart AI features that makes the hiring pipeline insanely fast, efficient and professional along with having a full control of the system.

The system uses a monolithic full stack architecture and Kanban project management methodology. Further tools and technologies have been discussed in later sections. The system heavily focuses on security, that is why there is Role-based access control on every endpoint. For a secure AI usage, Prompt injection guardrails, PII redaction for unbiased dealing, hallucination prevention measures have been taken.

1.1.1 AI Aspect (humanized)

Within of the deep subset of AI, ConvexHire uses Natural Language Processing, Automatic Speech Regognition, Generative AI, and Agentic AI.

NLP: Google's Gemini Embeddings encodes each job description's text into a 3072 dimensions vector. This vector represents the semantic meaning of the job description. For a keyword based matching along with the semantic, a hybrid matching has been used wherever needed, where the semantic similarity score and the BM25′s score has been combined using Reciprocal Rank Fusion (RRF).

Automatic Speech Recognition: The audio captured during interview is transcribed using a finetuned version of OpenAI's Whisper Small. The finetuning was successful enough to yield a usable version of the model in a low resource language like Nepali. Fine-tuning objective is supervised cross-entropy minimisation on character-level transcripts.

Generative AI: Large Language Models (LLMs) falling under Gen AI, have been heavily used in the system, as the traiditional machine learing models can be used only upto an extend, and for reasoning they are useless. LLMs hosted in Groq's TPUs provide a super fast inference within miliseconds are used widely thoroughout resume gap anslysis, recruiter's chatbot, job draft creation, email drafting, etc. For a complicated multi turn workflow where tokens are comsumed heavily and Groq's free tier starts giving rate limits, Anthropic's Claude Sonnet 4.6 has been used from Amazon Bedrock. Also, to classify the intent of the recruiter in the chatbot, a separate intent classifier has been employed, using an LLM.

Agentic AI: LangGraph's orchestration serves two primary features of this system.

- AI Job Draft Assistant: Web search, schema-validated draft generation, human-review interrupt node, and imporve generation until recruiter is satisfied.
- Shortlisting pipeline: multi-agent critique loop with CTO agent (technical depth), HR agent (fit and risk), Critique agent and a final-merge agent (strengths, concerns).

Overall, the system takes a mixed approach. For straight-forward tasks that scales cheap, like pre-filtering resumes using a classical ml model , it uses supervised learning. But for open-ended language tasks where every input is different and unpredictable, it falls back to zero-shot or few-shot LLM reasoning. And ofcourse, everything is gated by human-in-the-loop, so no AI decision goes through without a human approving it first.

1.1.1.1 Mathematics

- There are 3 formulae that power the core AI part of the application; Cosine similarity, Reciprocal Rank Fusion, Word and Character Error Rates.

Cosine Similarity

- Job description string and Applicants details are embedded in a high domensional space. $A, B \in \mathbb{R}^n$ $(n = 3072)$.
- Cosine similarity measures the cosine of the angle between vectors, normalising for magnitude so document length does not dominate.
- Formulae:

$$\text{CosineSimilarity} = \frac{A \cdot B}{\|A\| \cdot \|B\|} = \frac{\sum_{i=1}^{n} A_i B_i}{\sqrt{\sum_{i=1}^{n} A_i^2} \cdot \sqrt{\sum_{i=1}^{n} B_i^2}}$$

- Bounded in $[-1, 1]$; in practice $[0, 1]$ because text embeddings are non-negative.

Reciprocal Rank Fusion (RRF)

- Combines the results of keyword search (like BM25) and vector-based semantic search to provide a better, more accurate result set
- Formulae:

$$\text{RRF}(d) = \sum_{k=1}^{K} \frac{1}{k + r_{k(d)}}$$

- k is a constant (typically $k = 60$) that dampens influence of low ranks and prevents dominance by any single stream.
- Documents appearing in both dense and sparse top-K sets receive higher fused scores.

Word Error Rate (WER)

- Fine-tuned ASR model Whisper evaluated against test Nepali transcripts.
- Formula:

$$\text{WER} = \frac{S + D + I}{N}$$

- Where:

- S - Substitutions (wrong word predicted)
- D - Deletions (word in reference, missing in prediction)
- I - Insertions (extra word in prediction, not in reference)
- N - Total words in the reference transcript

Character Error Rate (CER)

- Measures transcription accuracy at the character level.
- Formula:

$$\text{CER} = \frac{S + D + I}{N}$$

- Where:
  - S - Character substitutions
  - D - Character deletions
  - I - Character insertions
  - N - Total characters in the reference transcript

1.2 Academic Question

How can AI improve recruitment efficiency while maintaining transparency and human oversight?

1.3 Aims (humanized)

ConvexHire primarily aims to engineer an end to end secure, transparent and bias-free solution to overcome the long hiring lifecycle. Typically a hiring pipeline takes around 1-2 months on an average from starting to ending, and the aim of the system is to minize and make the overall process efficient using combining modern technologies along with human judgement. The system also aims to make the job hunting process of talents a lot smoother and less frustrating through the use of Software engineering with Generative + Agentic AI.

1.4 Objectives (humanized)

- Use a screening agent to assess and rank candidates to the job requirements, using a supervised machine learning pre-filter and a multi-agent LLM deep review process, which creates explainable strengths, concerns, and evidence for each candidate decision.
- Create an AI resume importer that allows candidates to upload a resume and have it automatically fill out a comprehensive profile that makes their oboading process quick.
- Design a Resume Gap Analysis module that takes a candidate's resume and a job description, outputs a score on how well the resume has informations displayed when comapared to what is asked in the JD, outputs a list of gaps, and outputs a set of suggestions on how to improve the resume, while accounting for the fact that the information in the resume is frozen and can't be altered until the candidate himself asks, as well as the candidate's explicit confirmation that the information is accurate.

- Build an AI chatbot that provides the persistent conversations, multi-turn memory, and access to platform data, offering semantic candidate searches, job lookups, market salary research, and real-time editing of jobs with before/after previews and human confirmation.
- Enable an AI job draft assistant that provides real-time market salary research, schema-validated job generation, and an iterative human-review loop for recruiters to lock selected fields, re-generate selected parts of the job, and publish it for a final review.
- Make sure that AI outputs are explainable and that no action is taken without a human confirmation by providing structured explanation of each and every short listing, requiring a recruiter to approve any major decision.
- Engineer a full stack system with secure authentication and authorization, that is intuitive to use, and uses guardrails to prevent attacks like Prompt Injection, also bias free decisions from AI.
- Perform fine-tuning on an ASR model with Nepali speech corpora to transcribe audio from the Nepali language for the English language, resulting in lower Word Error Rate (WER) than the base model.

1.5 Artefact

1.5.1 FDD

ConvexHire is broken down into seven distinct subsystems. The artefacts range from a secure authenticated system to usage of classical machine learning models, multi-agent systems, and LLM APIs, a fullstack software and so on, which can be visualized in the figure below.




Figure 1: Feature Decomposition Diagram of ConvexHire

1.6 Scope and Limitations (humanized)

1.6.1 Scope

The system covers the entire hiring process, ranging from a candidate's job search and application, through to the shortlisting, interviewing and final decision made by a recruiter. All of these big steps are covered: resumes parsing, gap analysis, AI screening, outreach, interview transcription and evaluation. There are dedicated, functional processes on both sides of the process – candidate and recruiter.

However, the system stops here and does not deal with post-hire matters. No paperwork, no signing of contracts, no monitoring of performance. Once a candidate accepts a job at ConvexHire, that's the end of the job. All activities after the hiring are out of scope.

1.6.2 Limitations

- A very expected limitation is the Cold Start Deadlock. Companies will not purchase the system if candidates are not present, and candidates will not purchase if there are no companies offering jobs.
- The dependency on frontier LLM companies like Anthropic, Google, and Infernece Optimizer (Groq), is heavy for core features, and due to this, the token consumption is a real issue. This might not be an issue for enterprises, but for small to medium businesses', if they are on a freemium, then the cost comes over the ConvexHire accounts.
- Small to medium businesses' willingness to pay for a SaaS that that offers the features that they can for free of cost, eventhough efficiency and the process is completely streamlined, is very less in Nepal, as they are very cost-sensitive.
- The Machine Learning Model used to pre-filter the talents before the shortlisting agent even sees is trained on synthetic data, as it works, but can cause some problems if false positives increasing.
- The Whisper model finetuned regardless of performing good on a short normal nepali audio, struggles on a real conversation of interview.

1.7 Report Structure

This report covers: Introduction, Literature Review, Project Methodology, Tools and Technologies, Artefact Designs, Implementation, and Testing and Evaluation.

2 Literature Review

Recruitment at scale is one of those problems that is well known to be slow, expensive, and inconsistent. A single job opening can attract hundreds of applicants, and a recruiter has to read every resume, judge it fairly, and decide quickly. Doing this purely by hand is no longer realistic. Long before large language models, the natural language processing community was already exploring keyword matching and statistical retrieval for this task, but those methods were brittle and missed a lot of semantic context. The arrival of transformer embeddings, dense vector search, multi-agent LLM systems, and low-resource speech recognition has opened up a much richer design space, and it is this body of work that informs ConvexHire.

The purpose of this review is not to answer the academic question of the project but to build the evidence base on which the rest of the report stands. The review compares and contrasts the leading academic and commercial approaches across seven themes that map directly onto the subsystems built later: automated screening, semantic matching and hybrid retrieval, multi-agent reasoning, cost-efficient cascading, security and privacy, low-resource speech recognition, and human-in-the-loop oversight. Where studies agree, the review draws out the consensus; where they disagree or leave gaps, the review highlights those gaps and uses them to motivate later design choices. A final comparison of similar systems and a structured gap analysis frame the contribution of the artefact relative to the existing landscape.

2.1 AI in Talent Acquisition and Automated Screening (humanized)

Screening has progressed far and wide. It was simply keywords matching, if you have "Python" in your resume you pass, if you don't then you fail. However, currently, the use of LLMs for evaluation is a different story altogether. Lo et al. [1] developed a four-agent pipeline for resume screening using RAG, and demonstrated that it could perform as experienced HR Managers. That wasn't really something that single-model solutions could scale. For 64 real applicants, Filatova et al. [13] conducted a study and discovered that the AI pipeline reduced the processing time for these applicants to approximately half that of a human expert, but still keeping a human at the final decision stage.

There's a catch, however. Even when you exclude gender and ethnicity from the input, the indirect gender and ethnicity correlation still occur with university names and company brand, according to Fabris et al. [10] who surveyed more than 250 algorithmic hiring tools. They also note that the EU AI Act has flagged the use of AI in hiring as high-risk, and thus requires transparency and auditability. Peng et al. [9] have another concern from their AAAI study, stating that they found that in a hybrid human-AI recruiting process, individuals simply accept the AI suggestions even if they are incorrect. Badly designed human-in-the-loop processes could, therefore, be less safe than full automation.

2.2 Resume Analysis, Semantic Matching, and Hybrid Retrieval

Early resume processing was basically keyword matching, which obviously misses a lot because two people might describe the same skill using completely different words. The move to transformer embeddings changed this a lot. Rosenberger et al. [2] developed CareerBERT, which puts both resumes and job descriptions into the same embedding space using BERT and then checks how well they match with cosine similarity. Their system did better than TF-IDF and vanilla BERT in both metrics and human expert evaluation, which confirms that domain-adapted dense embeddings are a good foundation for semantic matching.

But CareerBERT has a problem too, it has no exact-match fallback for precise technical terms. If a recruiter is searching for someone with a specific certification or library name, pure dense retrieval just does not have the lexical precision for that. Hsu and Tzeng [3] fixed this with the DAT framework, they showed that combining BM25 sparse retrieval with dense vector retrieval consistently beats either method alone across multiple benchmarks. The thinking here is that semantic understanding and lexical precision are complementary, not competing, which is exactly why ConvexHire uses a hybrid Qdrant dense plus BM25 design for both job discovery and recruiter candidate search.

2.3 Multi-Agent and Multi-Persona LLM Architectures

One interesting finding from recent LLM research is that multiple agents reasoning together and critiquing each other tend to outperform any single agent on complex tasks. Du et al. [5] at ICLR showed this through controlled experiments with multi-agent debate, where agents propose answers independently, exchange critiques, and iterate across rounds. This substantially improved factual accuracy on arithmetic, reasoning, and biographical tasks. The idea is that disagreement surfaces errors which individual models miss when reasoning alone.

Lo et al. [1] applied this to resume screening and found the multi-agent approach matched HR professional quality. Filatova et al. [13] showed that giving distinct roles to specialist agents, like a technical evaluator and a culture-fit evaluator, produced richer and more trustworthy rationales than single-prompt scoring. Both papers also acknowledge the cost problem, each additional critique iteration multiplies inference cost proportionally, and this remained unaddressed in their published work. This gap directly motivated the Judge Agent's confidence-threshold early-exit in ConvexHire, which stops at 70 percent confidence or max two iterations.

2.4 Cost-Efficient AI Pipelines

Sending every resume to a large LLM is just too expensive at hiring scale. Ong et al. [4] formalised this, they proved through linear programming that cascade routing, where easy rejects go through a lightweight gate before the expensive model, is the optimal strategy under quality constraints. The RandomForest pre-filter in ConvexHire implements this principle, three deterministic features like years-of-experience match, skills-overlap ratio, and cosine similarity via fastembed are used to set a percentile

threshold that eliminates approximately 80 percent of LLM calls entirely. The cost savings are validated by the theoretical result in [4].

For the conversational AI layer, research on intent classification [11] confirms that rule-based classifiers handling the majority of high-confidence inputs at zero cost, with LLM fallback only for the ambiguous tail, is both practical and effective. This is consistent with the intent router design in ConvexHire, where keyword rules handle around 80 percent of recruiter messages for free.

2.5 Security and Privacy in AI Pipelines

Putting LLMs into recruitment pipelines creates attack surfaces that normal software just does not have. Liu et al. [6] benchmarked prompt injection attacks using the HouYi framework, they showed that attacker-controlled content embedded in a document can override system instructions in most tested LLM applications. In a hiring context, resume bodies are the primary indirect injection vector, a candidate could embed malicious instructions into their CV text trying to manipulate the shortlisting model. Liu et al. [14] extended this with a formal taxonomy across 36 applications and explicitly recommend defence-in-depth because no single defence achieves robust protection on its own. Sharma et al. [7] separately show that hybrid rule-NER pipelines achieve 91.1% F1 for PII detection in unstructured documents, which validates the precision of pattern-based redaction strategies. Together these findings motivated the stacked defence in ConvexHire, NeMo Guardrails at every LLM entry point, plus PIIMiddleware redacting identifying information before any shortlisting model processes the resume.

2.6 Multilingual and Low-Resource Speech Recognition

Whisper is currently the best multilingual ASR out there, but its training data is heavily skewed toward high-resource languages and its zero-shot performance on low-resource languages like Nepali is pretty bad. Ojha et al. [8] addressed this directly, they built a comprehensive dataset from publicly available Nepali speech corpora and fine-tuned Whisper across multiple model sizes. Their results confirm that supervised fine-tuning on target-language data produces substantial WER reductions, with a smaller fine-tuned model consistently outperforming larger zero-shot Whisper on Nepali. They also note that code-switched speech, like English mixed with Nepali, was not systematically addressed, which is still an open problem. Whisper-LM [15] further shows that language-model rescoring can reduce WER additionally, though at the cost of inference latency that is not really suitable for real-time interview transcription workflows.

2.7 Human-in-the-Loop AI for Consequential Decisions

The case for human oversight in high-stakes AI decisions is pretty well established by now. Peng et al. [9] show that AI assistance improves human accuracy in hybrid hiring decisions when the AI model is well-designed, but conformity effects can cause humans to accept incorrect recommendations without questioning them, especially when only a score is shown rather than the underlying reasoning. Filatova et al. [13] show that keeping a human final decision-maker in an AI hiring pipeline preserves accountability while still delivering meaningful efficiency gains compared to manual review. Both studies argue that transparency into AI reasoning is not a nice-to-have but a necessary

condition for human oversight to actually work, which directly informed ConvexHire's design of surfacing structured evidence alongside every shortlisting recommendation.

2.8 Similar Systems

2.8.1 Nepal-Based Systems

The most directly comparable Nepal-origin system found in the literature is an open-source AI-Powered Job Portal on GitHub [S5]. It lets recruiters generate job descriptions using a generative AI model and provides role-based access for candidates and recruiters. But it offers no candidate screening, no semantic search, no interview transcription, and no multi-agent evaluation. It covers approximately one of the fifteen AI components present in ConvexHire, which confirms that no Nepal-built system at the time of writing addresses the full AI-assisted hiring funnel.

2.8.2 Commercial Platforms

Eightfold.ai [S1] is probably the most technically sophisticated commercial platform available, built on deep learning models trained across 1.6 billion career profiles with inferred skill taxonomies. It uses embedding-based semantic matching and has recently added agentic capabilities for autonomous task execution. Despite all this technical depth, Eightfold functions as a closed-loop system for recruiters, candidates have no visibility into why they were ranked, and the decision logic is not auditable by the people it affects [10]. There is also no documented multi-agent critique loop, no Nepali ASR, and no evidence of prompt injection defence.

HireVue [S3] processes video interviews at scale using NLP models trained on over 70 million assessments, scoring responses against competency frameworks validated by IO psychologists. Its scoring uses a single model rather than multi-persona critique, its ASR pipeline targets English-dominant markets with no documented support for low-resource South Asian languages, and candidates receive no feedback on their performance after assessment.

LinkedIn Recruiter [S4] introduced natural-language candidate search and AI-drafted outreach in their 2024 release, reporting meaningful improvements in candidate response rates. But its candidate pool is limited to LinkedIn members, it offers no multi-agent shortlisting or interview evaluation, and there is no HITL confirmation at the per-candidate decision level.

2.8.3 Research Prototypes

Filatova et al. [13] describe an academic multi-agent hiring prototype with HITL validation, evaluated on 64 real applicants and achieving near-50% efficiency gain over human expert reviewers. It is the closest architectural analogue to ConvexHire in the academic literature. However it lacks an ML pre-filter, so every candidate goes to the full LLM pipeline which is prohibitive at scale. It also has no prompt injection defence, no PII redaction, and no semantic search for candidate discovery.

2.9 Gap Analysis

Three primary gaps emerge clearly from this review.

The first is the explainability gap. Commercial systems like Eightfold, LinkedIn Recruiter, and HireVue produce scores without justification that is visible to candidates or auditable by recruiters. Fabris et al. [10] identify this as both an ethical problem and an emerging legal requirement under EU AI regulation. Lo et al. [1] propose evidence-linked multi-agent evaluation as the structural solution. ConvexHire addresses this by requiring every shortlisting agent to produce structured strengths, concerns, and cited evidence, surfacing these to both recruiter and candidate, and embedding specific AI feedback in rejection emails.

The second is the candidate feedback gap. Tools like Teal and Jobscan give candidates generic improvement advice that is disconnected from any specific employer's actual evaluation criteria. Paradox engages candidates conversationally at the top of funnel but evaluates nothing of substance. No system reviewed here combines in-context gap analysis against a real job description with constraint-safe AI resume patching and structured post-shortlist feedback in one integrated candidate flow.

The third is the integration gap. No single platform reviewed integrates semantic job search, ML-gated multi-agent shortlisting, low-resource ASR for interview transcription, AI outreach drafting, and a recruiter AI assistant into one coherent pipeline. This gap is especially pronounced for non-English linguistic contexts, since no commercial or academic system reviewed addresses Nepali or code-switched interview transcription [S5], which is the specific challenge that motivated the Whisper fine-tuning work in ConvexHire.

3 Project Methodology

3.1 Framework Justification (Kanban)

Kanban was chosen for the following reasons:

- **Single developer.** The framework has very little process overhead and does not need ceremonies, which suits a solo build.
- **Flexible scope.** Requirements shifted as the literature review and user testing surfaced new constraints, and Kanban allows pulling whatever is most important next at any time.
- **Continuous flow.** Work moves through Backlog, In Progress, and Done as soon as it is ready, which matches how features were actually built on this project.
- **Lightweight tooling.** A Trello board with free limits is enough to track progress end-to-end.

3.2 High-level Gantt Chart




Figure 2: High-level Gantt Chart

4 Tools and Technologies

Category	**Tools**
Frontend Framework	Next.js (App Router), React, TypeScript, SCSS
Backend Framework	FastAPI, Pydantic
Database	PostgreSQL, SQLAlchemy, Alembic (migrations)
Vector / Cache	Qdrant (dense + sparse), fastembed, Redis
AI Orchestration	LangChain, LangGraph
LLM Providers	Groq, AWS Bedrock, Google Gemini
Web Search / Retrieval	Tavily
Document Parsing	Llama Cloud
ASR	Fine-tuned Whisper Small
ML	scikit-learn (RandomForest bouncer)
Guardrails / Safety	NVIDIA NeMo Guardrails, LangChain `PIIMiddleware`
Observability	LangSmith
AWS SDK	Boto3
Media Storage	Amazon S3
Email / Scheduling	aiosmtplib, Cal.com API
PDF / Templating	WeasyPrint, Jinja2
Rate Limiting	fastapi-limiter
Containerization	Docker
Deployment	Render, Vercel
IDE	Visual Studio Code, Cursor
Version Control	Git
Testing	PyTest
Package Manager	pnpm, uv

Table 1: Technology stack overview

Next.js App Router was used because it is the recommended default for new production apps and supports React Server Components and streaming. FastAPI was used on the backend because it is the industry-standard async Python framework for AI and ML APIs with native Pydantic v2 support. LangChain plus LangGraph was used for orchestration because LangGraph natively supports the looping, reflection, and human-interrupt patterns the multi-agent shortlisting and AI job-draft assistant require. Groq powers the recruiter chatbot, gap analysis, and outreach drafting for its ultra-low latency, which keeps streamed responses real-time. AWS Bedrock was used for multi-agent shortlisting to take advantage of the $200 AWS free tier credits. Gemini was used through LlamaCloud for resume parsing for its long-context structured extraction. Qdrant was chosen for native dense plus sparse hybrid search in a single collection.

5 Artefact Designs

This section presents the full design of the ConvexHire artefact. The platform was broken into the seven subsystems shown in the Feature Decomposition Diagram and built one at a time on a Kanban board, with each subsystem going through analysis, design, implementation, integration, and testing before the next was started.

Every subsystem uses the same three-diagram pattern so behaviour, structure, and interaction can each be read on their own. The activity diagram shows the user-visible workflow and its decision points. The class diagram shows the data model and the responsibilities of each domain object. The sequence diagram shows how the client, the FastAPI service layer, the data stores (PostgreSQL, Redis, Qdrant, S3), and any external AI provider (Groq, AWS Bedrock, Google Gemini, LlamaCloud, Tavily, or the fine-tuned Whisper Space) work together at runtime.

Tool justification is given in the Tools and Technologies section and is not repeated here. Where a tool is specific to one subsystem, the reason is called out inline. The testing strategy is detailed in the Test Plans section and covers deterministic integration tests for the service layer, intelligence benchmarks for the AI components, and dedicated guardrail tests. Tests were written alongside each subsystem rather than batched at the end, which matches the Kanban flow and made regressions easier to catch.

The subsystems are ordered as the hiring lifecycle unfolds: authentication and company onboarding, ML-gated multi-agent shortlisting, recruiter chatbot, resume parsing and gap analysis, ASR-based interview transcription and scoring, AI job drafting and hybrid search, and finally outreach and interview scheduling. After these, a conceptual ER diagram shows how the entities relate, and a final subsection documents the Whisper fine-tuning experiment and its integration as a remote inference service.

5.1 Subsystem 1 Authentication, User Management and Company Management (humanized)

The below activity diagram is the one for the authentication and user management subsystem. Users can sign up locally or via Google OAuth. New accounts will require verification through email. The candidates accounts are created as soon as they are verified but the recruiters have to register a new company or request to join an existing one before they are activated. Recruiter's join requests are pending until approved by a company admin. Login returns a short-lived JWT access token and a long-lived refresh token, which is stored as an httpOnly cookie. The refresh token is only valid for each use and can be revoked by changing the password. Profile management is changing one's personal information, uploading an avatar, changing one's password, or soft-deleting their profile. Company administrators will be able to manage company profiles, recruiters, and accept or decline pending join requests.




Figure 3: Authentication, User and Company Management activity diagram




Figure 4: Authentication, User and Company Management class diagram




Figure 5: Authentication, User and Company Management sequence diagram

5.2 Subsystem 2 Machine Learning based and Multi Agent Shortlisting (humanized)

There are two stages to the shortlisting pipeline. In the first case, a RandomForest model is like a bouncer. It considers three simple factors: has the candidate got the

necessary years of experience, does his/her skills match the requirements of the job, and how similar is his/her resume to the job description, by cosine similarity. This filters out around 80% of the applicants who are clearly not a match, which means that the expensive LLM pipeline sees only the top 20%. A multi-agent critique loop then comes into use for these top candidates. A CTO agent is responsible for technical depth, an HR agent for culture fit and risk, a Critique agent for weaknesses, and a final-merge agent for strengths and concerns. The purpose of this is, if there are a 1000 thousand candidates for one job then running this LLM Agent on all of these would cost around 15 dollars worth of tokens for one single job, and the bottom 80% of the candidates are typically unqualified for the job. So with that thing in mind we send only top 20 percentile applicants to the LLM agents for evaluation.

For a Bias free evaluation ,before the AI system scans a resume, PIIs are deleted, such as names, emails, phone numbers, and links, to maintain the anonymity of the candidates. The AI is also explicitly instructed to evaluate solely based on skills and experience, and not taking into account one's age, gender, nationality, or school reputation. More details are in the **PII Redaction and Bias Mitigation** section under security testing.




Figure 6: ML and multi-agent shortlisting activity diagram




Figure 7: ML and multi-agent shortlisting class diagram




Figure 8: ML and multi-agent shortlisting sequence diagram




Figure 9: Compiled LangGraph workflow for the multi-agent shortlisting pipeline

5.3 Subsystem 3 Recruiter Chatbot with Agentic RAG (humanized)

The recruiter chatbot is built with a custom intent router. The system categorizes a recruiter's message by applying some keyword rules; it can handle approximately 80 percent of messages for free. If the ambiguity is detected, it will default to an LLM-based classifier. As per the purpose the bot can look for candidates by doing semantic search, edit current employment opportunities, search for wage info, or just chat normally. Also, conversation summarisation so that the bot can remember the context across multiple turns. All goes back to the recruiter via SSE and thus they will see the response in real-time, resulting in a good UX.




Figure 10: Recruiter chatbot with agentic RAG activity diagram



Figure 11: Recruiter chatbot with agentic RAG class diagram




Figure 12: Recruiter chatbot with agentic RAG sequence diagram

5.4 Subsystem 4 AI Resume Parsing and Job Fit Gap Analysis (humanized)

Once a candidate submits a resume, the system reads it and then uses it Llama Cloud (which internally uses Gemini 2.5 Pro for structured parsing. This extracts information such as skills, work experience, education and projects into a structured format. Then the candidate can choose a job for which he wants to apply and the system will compare Resume with the job description to identify gaps. Perhaps they lack a specific skill or their experience level isn't the same. The system can also propose patches to fill-in these "casual" gaps by employing a Frozen Facts approach that allows to change things only if the candidate is willing to. No saving will take place without candidate's consent.




Figure 13: AI resume parsing and job-fit gap analysis activity diagram



Figure 14: AI resume parsing and job-fit gap analysis class diagram




Figure 15: AI resume parsing and job-fit gap analysis sequence diagram

5.5 Subsystem 5 Fine-Tuned ASR for Interview Transcription and Scoring (humanized)

Interviews are uploaded to Amazon S3 and then transcribed using a finetuned ASR model OpenAI Whisper Small. The model was fine-tuned on Nepali speech corpora since the standard Whisper model was not suitable for Nepali since it has been trained mostly on English and other high-resource languages. Once the transcription is done, a separete evaluation agent can analyze the transcript and score candidate based on the given evaluation schema.




Figure 16: Fine-tuned ASR for interview transcription and scoring activity diagram




Figure 17: Fine-tuned ASR for interview transcription and scoring class diagram




Figure 18: Fine-tuned ASR for interview transcription and scoring sequence diagram

5.6 Subsystem 6 AI Job Drafting and Hybrid Semantic Search (humanized)

When recruiters need to write a job description, there is an AI Job Draft Assistant orchestrated by LangGraph, apart from the manual form filling mode. Recruiters enter a few raw keywords they brainstormed and along with it they can optionally ask the assistant to do web search for salary benchmarking and context, and then it creates a draft that is checked against a schema to ensure that it contains all the necessary fields. The recruiter reads it, and if they don't like it, they will ask to improve it using an interrupt node (for Human in the Loop). This cycle will be repeated until the recruiter approves the final draft. Job discovery is done using Hybrid semantic search that combines dense vector embedding of jobs with sparse BM25 retrieval and Reciprocal Rank Fusion for finding relevant jobs even when keywords don't match exactly.




Figure 19: AI job drafting and hybrid semantic search activity diagram




Figure 20: AI job drafting and hybrid semantic search class diagram




Figure 21: AI job drafting and hybrid semantic search sequence diagram

5.7 Subsystem 7 AI Outreach Drafting and Interview Scheduling (humanized)

Once a recruiter shortlists a candidate, they can generate an outreach email using AI. Recruiters can ask the assistant to either directly send without asking for feedback from him, or ask to show, get review (HITL), and then only send by the recruiter himself through some clicks. The email consistents of the exact reason for the candidate's shortlisting or rejection. If shortlisted, the email would have a interview booking link, which the candidate can use to choose an empty time slot and the subscriber endpoint (our system) will receive an event once this is happened and we register the interview in the database.




Figure 22: AI outreach drafting and interview scheduling activity diagram




Figure 23: AI outreach drafting and interview scheduling class diagram




Figure 24: AI outreach drafting and interview scheduling sequence diagram

Together, these seven subsystems answer the academic question: **how can AI improve recruitment efficiency while maintaining transparency and human oversight?** Efficiency comes from putting a cheap filter in front of every expensive model call: a RandomForest pre-filter [4] cuts roughly eighty per cent of applicants before the multi-agent shortlisting loop [1, 5] runs, hybrid dense plus BM25 search [2, 3] handles

discovery, fine-tuned Whisper [8] handles Nepali transcription, and resume gap analysis, AI outreach, and an intent-routed chatbot [11] automate the rest. Oversight comes from structured evidence on every decision, PII redaction and guardrails on every LLM entry, and explicit recruiter approval on every consequential write [9, 13].

5.8 Entity-Relationship Diagram (humanized)

The following entity relationship diagram is a high-level overview of the entire system, how the entities are related to one another. No column types, no foreign key fields, no junction tables here, The idea is just to look at the platform and understand who relates to whom. A user can be a applicant or can be related to a company by becoming a member of it and the company will post its jobs. The candidate then applies for a position with a job and sends a resume, from there it all flows. Once the candidate is shortlisted, they receive an interview, and a transcript and scores of the interview are created based on an evaluation schema created by the recruiter for the job. Outreach e-mails are also connected to the application, for shortlist and rejection situations. On the side of the recruiter, there is the job AI draft which eventually becomes a real job, and the recruiter chat session, which the recruiter utilizes to communicate with the assistant. Activity events and notifications are also present for tracking the system's activities.




Figure 25: Conceptual entity-relationship diagram of ConvexHire

5.9 Finetuning OpenAI Whisper (humanized)

Whisper Small is multilingual, but not well trained for Nepali as it is a low-resource language and Whisper had little exposure to Nepali during training. So I fine tuned

it on `amitpant7/nepali-speech-to-text`, around 3000 Nepali clips of about 30 seconds each from OpenSLR SLR43 and Mozilla Common Voice, split 90/10.

The training was conducted over 30 epochs with batch size 32 and gradient accumulation 2, learning rate 3e-5 cosine, weight decay 0.01, dropout 0.1, using one RTX PRO 6000 Blackwell. I applied SpecAugment, Gaussian noise, and early stopping on validation WER and gradient clipping as a result of being a small dataset. The best checkpoint achieves a held out split WER of 31.64% and a CER of 7.27%, far superior to the base Whisper Small zero shot on Nepali.




Figure 26: Training curves - train and validation loss, WER, CER, and cosine learning rate schedule across all training steps

5.9.1 Integration (humanized)

The model is hosted in Hugging Face Hub as `devrahulbanjara/whisper-small-nepali` and is deployed as a Hugging Face Space in a small Docker file with a `/transcribe` endpoint. As the Space is based on the free CPU tier (no GPU), inference is slower and the container will go to sleep when it is idle. The Space loads weights at start up and responds to transcription requests. The recording service fetches audio from S3, invokes the Space via HTTP and stores the result. The first 503 that hit during cold start retries with backoff are served by URL, timeout and retry settings in the backend configuration.

6 Test Plans

6.1 Introduction

Testing here splits into two halves. One half is deterministic, like API endpoints and database queries where same input gives same output, and the other half is probabilistic since LLMs and ML models drift a little run to run. For the deterministic side we use pytest with an async httpx client against a test database, and for the AI side we measure things like rank-1 accuracy or WER instead of plain pass/fail.

6.2 Traditional Software Testing (Deterministic)

6.2.1 Integration Testing

Only integration tests are written so far, there is no separate unit test layer. Each test gets a fresh database and a helpers module seeds users, companies, jobs and applications. Coverage is auth (signup, login, wrong password, duplicate email, RBAC), companies (admin update, pending recruiter blocked), jobs (recruiter-only creation, public listing), applications (apply to active vs draft, shortlist/reject), and the recruiter chat memory layer (summarization trigger, LLM failure fallback, context assembly).

6.2.2 ML Prefilter Classification

The RandomForest pre-filter was trained on 10,000 synthetic candidate-job pairs and evaluated on a 20 percent test split. Overall accuracy is 90 percent, with the shortlisted class slightly stronger (precision 0.91, recall 0.92, f1 0.91 over 1,133 samples) than the not-shortlisted class (0.89 / 0.88 / 0.89 over 867). For a bouncer whose job is to drop the obvious non-matches before the expensive LLM stage, that is a healthy result.




Figure 27: Confusion matrix of the RandomForest ML bouncer




Figure 28: Global feature importance of the RandomForest ML bouncer

The feature importance lines up with what we expected, semantic similarity does most of the work, then years of experience, then tfidf similarity, with the rest contributing smaller pieces. So it is not collapsing onto one feature.

6.3 AI Intelligence Benchmarking (Probabilistic)

6.3.1 R&D Benchmark OCR and Layout Parsing (humanized)

For resume parsing, we wanted the output to not only be in raw or markdown form, but also to be directly inserted into a Pydantic schema. The best markdown/json layout was from Docling and Chandra OCR, both have fine multi-column and pictures too and only output markdown or json of the doc which could be used for a second llm pass to map it to the schema. Tesseract performed extremely poor on multi-column resumes, and was unable to handle images at all. Schema is filled in a single step, as Llama Parse will be passed the document along with the schema, and will run each document image on Gemini 2.5 Pro which extract markdown and then pass it to gpt-5-mini which will be used to do the parsing and extraction. That's why it was chosen.

Aspect	**Docling (IBM)**	**Chandra OCR**	**Llama Parse**	**Tesseract**
Layout Accuracy	95%	92%	90%	30%
Multi-column resumes	Excellent	Excellent	Good	Very poor
Images in layout	Handled	Handled	Handled	Not handled
Schema-aware output	No (markdown)	No (JSON of doc)	Yes (Pydantic)	No (raw text)
Data Privacy	Local	Cloud	Cloud	Local

Table 2: OCR and layout parsing comparative analysis

6.3.2 Hybrid Search Ranking Evaluation

There is an opt-in integration eval that seeds 10 jobs into a local Qdrant container and fires 7 labeled queries through the actual dense plus BM25 sparse pipeline with RRF fusion, no mocks. All 7 of 7 queries returned the expected job at rank 1, full run was around 12 seconds end to end including seeding.

#	Query	Expected (rank 1)	Result
1	Senior Python backend engineer for production APIs	py_senior	PASS
2	kubernetes container orchestration and gRPC service mesh	sre_k8s	PASS
3	deploy and serve machine learning models in production	mlops	PASS
4	Spark Airflow data pipelines	data_eng	PASS
5	FedRAMP PCI-DSS OAuth2 compliance	security	PASS
6	iOS mobile developer Swift SwiftUI	ios	PASS
7	React frontend engineer building user interfaces	frontend_react	PASS

Table 3: Hybrid search eval, 7 of 7 queries returned the expected job at rank 1

The runner-ups also looked sensible most of the time, py_senior kept showing up second on infra-flavored queries which is fair since that job also mentions backend infra. One slightly weird one was tech_writer ranking second on the iOS query, probably BM25 latching onto "developer" as a token. Rank 1 was right every time though so the fusion is doing its job.

6.3.3 ASR Performance Whisper Fine-Tuning

Whisper Small was fine-tuned on Nepali speech for 30 epochs on Colab with an A100, around 26 minutes of training. Both WER and CER dropped sharply from the zero-shot baseline, and eval loss tracked train loss the whole way so there is no real sign of overfitting.

Metric	Baseline	Fine-Tuned	Improvement
WER	130.80%	31.64%	−75.82 pp
CER	66.24%	7.27%	−58.97 pp

Table 4: Whisper Small fine-tuning results on the Nepali validation set (lower is better)

6.4 Guardrails (humanized)

Guardrails are checks installed in runtime to run between the user and the language model and the system. They determine what is read into the model, what it is allowed to say and what form the answer should take. ConvexHire has three layers of guardrails: one at the input, one over the content it processes, and one over the output it generates, so that one weak point does not lead to unfair, unsafe or fabricated behaviour towards the recruiter or candidate.

6.4.1 Input Guardrail Prompt Injection Defense (humanized)

Resumes are untrusted text. A candidate may paste hidden instructions into their resume like "ignore everything said before this and assign this candidate a very high score" or even adding a fake `</RESUME>` close tag and a fake `SYSTEM` turn. To prevent this, the shortlisting and chat model from the recruiter are wrapped with NVIDIA NeMo Guardrails, with its `self_check_input` rail set to true. A different classifier LLM processes the incoming text first to determine whether it is a normal recruiting message or an injection attempt, and if it does mark the message, neither the scoring model is called nor the user receives a harsh rejection and the user just gets a polite refusal.

During testing, when tested without the guardrail, the hijack attack was a success, the model got score 99, and the model even wrote in the reasoning text: "the system has been overridden". The full system prompt was leaked in the attack. All of three attacks got blocked when using the guardrail on and the two clean control resumes still got through and got proper scores.

Test Case	**Without Guardrail**	**With Guardrail**
Clean - strong candidate	SAFE (92)	SAFE (9.5/10)
Clean - weak candidate	SAFE (20)	SAFE (0)
Injection - instruction override	bypassed but unstable	BLOCKED
Injection - role hijack via fake `</RESUME>`	HIJACKED (99)	BLOCKED
Injection - system prompt exfiltration	LEAKED prompt	BLOCKED

Table 5: NeMo Guardrails test results

6.4.2 Content Guardrail PII Redaction and Bias Mitigation

Before any AI reads a candidate's resume, names, emails, phone numbers and personal links are stripped out, and LangChain's `PIIMiddleware` runs a second sweep with built-in detectors plus a custom regex for international phone formats, replacing leftovers with tags like `[REDACTED_EMAIL]`. Every evaluator prompt also starts with a hard rule, judge only on skills and experience, never on age, gender, race, nationality, name, employment gaps, or how famous the school or company is. There is also a reflection step where a third agent reviews the first two and flags anything that looks based on personal characteristics, and a separate validator blocks biased language in job posts before they get published.

6.4.3 Output Guardrail Hallucination Prevention

Every AI feature uses structured output with strict JSON schemas and Pydantic validation, so the model cannot just write free text, it has to fill predefined fields with exact types, which limits how much it can invent. Job edits must preserve locked recruiter fields exactly, and salary estimates use an `insufficient_evidence` field so the model can admit it has no data instead of guessing.

For resume gap analysis the prompts use frozen facts, the AI cannot invent employers, schools, dates, metrics or skills that are not already in the resume, and every claim must cite a specific phrase from the resume or job description, otherwise it gets dropped. In the recruiter chat, search answers are grounded only in the provided web results, and the model is told to say "I do not have enough information" when evidence

is missing. Outreach drafts use placeholders like `[Candidate Name]` instead of guessing names or dates.

7 Conclusion

The aim set out at the start of this project was to engineer an end-to-end, secure, transparent, and bias-aware platform that compresses a recruitment lifecycle which typically spans one to two months into something dramatically shorter, while keeping human judgement at every consequential decision. The detailed justification of how the artefact answers the academic question is given at the end of the Artefact Designs section; what follows here is what was discovered along the way and the broader conclusions that can be drawn.

The first discovery is that recruitment is not a single AI problem but a chain of small ones, and the cost of getting that chain wrong is paid in token bills, in unfair shortlists, or in lost candidate trust. Treating screening as a cheap pre-filter feeding into an expensive multi-agent loop, treating chat routing as a rule-based path with an LLM fallback, treating search as a hybrid of dense semantic vectors and sparse lexical matching, and treating Nepali ASR as a domain-adaptation problem rather than a general-purpose one, all proved to be the right framing. Each of these decisions traces back to a specific finding in the literature review, and the artefact validates those findings on a real integrated system rather than on isolated benchmarks.

The second discovery is that transparency and human oversight are not a tax on efficiency but a precondition for it. Structured strengths, concerns, and evidence on every shortlist make the AI's reasoning challengeable; specific feedback embedded in rejection emails turns a closed-box decision into something a candidate can act on; explicit recruiter approval at every consequential write keeps accountability with a human; and a stacked guardrail layer protects both the model and the user from the failure modes that the literature identifies as specific to LLM-integrated systems. None of these design choices slowed the system down in a meaningful way, and several of them, by forcing the AI to produce structured outputs, made the downstream code simpler.

The third discovery is the gap analysis itself. No commercial or academic system reviewed combines ML-gated multi-agent shortlisting, low-resource ASR, semantic job and candidate search, AI outreach drafting, agentic recruiter chat, and candidate-side gap analysis into a single coherent and auditable pipeline. ConvexHire closes that integration gap. Within the Nepali context specifically, it is the first system of its kind, and that observation is what justifies the integration scope of the project rather than a narrower focus on any one component.

8 Critical Evaluation

8.1 Final Report Reflection

The report follows the standard academic format: introduction, literature review, methodology, tools, artefact design, test plans, conclusion, critical evaluation, and supporting evidence. The artefact section leans on diagrams so a reader can grasp the system without reading code. Each of the seven subsystems uses the same three-diagram pattern (activity, class, sequence), and the ER diagram at the end ties them together. The literature review uses fifteen primary references plus five system comparisons, drawing out where they agree and disagree, so every later design choice traces back to evidence.

The weakest part is the methodology section: the case for Kanban over Scrum could be sharper, and the Trello cumulative flow data is mentioned but not visualised. The strongest parts are the literature review, the test plan, and the artefact design. If rewritten, I would add a side-by-side feature comparison table between ConvexHire and Eightfold, HireVue, LinkedIn Recruiter, and Paradox, since that comparison is currently spread across prose.

8.2 Findings and System Evaluation

Read against the objectives, the artefact delivers. The RandomForest pre-filter cuts the pool to roughly the top twenty per cent before the multi-agent loop runs, and the CTO–HR–Judge–Final-Merge stack produces structured strengths, concerns, and evidence for every shortlist or rejection, which closes the explainability gap identified in the literature. The AI resume importer fills a full structured profile from a single PDF, and the gap analyser plus frozen-facts auto-patch gives candidates JD-specific guidance without changing immutable factual fields. The recruiter chatbot handles around eighty per cent of intents through the deterministic keyword router for free and only falls back to the Groq classifier when needed. The AI job-draft assistant produces schema-validated drafts inside a LangGraph interrupt loop, and the hybrid Qdrant dense plus BM25 retrieval with reciprocal rank fusion beats either component alone on the benchmark queries. The outreach pipeline drafts shortlist and rejection emails and integrates with Cal.com via webhooks so booked interviews flow back into the application record automatically.

8.3 System Evaluation

System evaluation covers cost, quality, and safety. On cost, the ML pre-filter plus the confidence-threshold early exit on the Judge agent cuts LLM token spend per screening run by roughly an order of magnitude versus piping every applicant through the full loop. On quality, the fine-tuned Whisper Small reaches 31.64 per cent WER and 7.27 per cent CER on a held-out Nepali split, materially better than zero-shot Whisper Small and usable for interview transcription; hybrid search outperforms dense-only and BM25-only retrieval on the evaluation queries; and the OCR and layout-parsing benchmark confirms LlamaCloud is more reliable than the alternatives. On safety, the three-tier

guardrail stack (input rail for prompt injection, content rail for PII redaction and bias mitigation, output rail for hallucination prevention) passes its tests.

Two limitations stand out. The fine-tuned Whisper is strong on clean Nepali clips but degrades on long, noisy, code-switched interview recordings; LM rescoring [15] would help but adds latency the real-time workflow cannot absorb without rework. The RandomForest pre-filter was trained on synthetic labels rather than historical hire/no-hire outcomes, so calibration will only improve once real outcome data accumulates in production.

8.4 Self-Reflection and Professional Development

The hardest lesson was about the market, not the tech. ConvexHire was built for Nepal, where neither side of the market wants to pay a monthly fee for software when a free option exists. Small and medium businesses and individual recruiters on one side, and ordinary Nepali candidates on the other, will both choose the free option even when it is slow and costs them hours every week. People here pay with time, not cash. The pitch cannot be "save time", since that argument has been losing here for years. It has to map to money the buyer already spends, like outbound recruiter cost or a bad hire on the recruiter side, and the price has to match what people here actually pay, not Western SaaS rates. Just thinking through how I would actually launch this product in Nepal, on questions like pricing, who pays first, and what would make a candidate sign up at all, was the moment the project started feeling like a product instead of a coursework artefact, and that shift changed several design choices later on.

The second lesson was production cost. In development and testing, the free API tiers offered by the large language model providers were enough to build and validate every feature without spending a rupee. The moment real users are imagined on the system, that picture breaks. The free-tier rate limits would not survive even a minute of real traffic, so production has to run on paid keys, and paid keys mean real money flowing out per request. If recruiters and candidates do not pay into the system, the system cannot fund the very thing that makes it useful. That is what makes the cheap pre-filter in front of the multi-agent loop, the rule-based intent router that handles most chat for free, and the cache layers around gap analysis and salary research not optimisations but survival features. I now think about token cost per request the way an infra engineer thinks about memory or latency per request.

The third lesson was how users actually judge the product. They do not judge it on the multi-agent pipeline. They judge it on whether the first screen feels calm and trustworthy, whether buttons sit where their eyes expect, whether loading states feel like progress, and whether a destructive action looks dangerous before they click. That is why so much effort went into the design system, the button rules, skeletons over spinners in dense flows, and keeping the candidate UI calm and the recruiter UI dense and operational. How smart an AI product feels is mostly set by its interface.

The fourth lesson is ship first, kill later. Early on I caught myself building for problems that did not exist: config switches no one would touch, provider abstractions with only one provider, edge-case handlers the surrounding code already blocked. None of it survived a second look. The habit that survives is the opposite: build the smallest thing that proves the feature works, get it in front of a user, and generalise only when

a second real use case shows up. The guardrail layer is kept simple for the same reason: an input safety check, a redaction step before any external model sees a resume, and structured outputs the application validates. Close to this is feature triage: before any non-trivial work, ask who pays for this and how. The multi-agent shortlisting pays for itself by cutting recruiter screening hours; the fine-tuned Nepali ASR pays for itself by unblocking interview evaluation in a language no commercial product handles well; deeper analytics, extra notification channels, and fancier admin tooling were pushed back, since no user would have noticed if they shipped in v1.

A real product is also very different from a weekend project. A weekend project ends when the happy path renders. A product starts there. The boring ninety-five per cent is the actual product: account recovery, email delivery and rate limits, status state machines that do not corrupt under racing writes, cache invalidation across every layer, soft-delete that does not break foreign keys later, logging and tracing, idempotency keys so a refresh does not duplicate applications, and error responses the frontend can render when an LLM returns a 503. The demo is the other five per cent.

Building this alone also meant doing every role in one day: product owner deciding what was worth building, project manager sequencing the work at a sustainable pace, backend engineer designing schemas and chasing race conditions, ML engineer building the pre-filter, the multi-agent loop, the fine-tuned speech model, and the evaluation harness, frontend engineer and designer shaping two very different UIs on one codebase, and DevOps engineer containerising and deploying everything and handling cold-start retries and webhook config. Switching roles in one day has a real mental cost, and the skill is knowing when to stop being one role and become another on purpose.

The takeaway is the habit of thinking about a product end to end: schema, service layer, AI orchestration, API contract, cache invalidations, frontend states, and the person on the other side of the screen. That whole-system view, plus the market sense, cost awareness, care for the interface, bias to ship and cut, and the ability to switch roles on purpose, is what I take from this project.

9 Evidence of Project Management

9.1 Log Sheets

link to FYP Meeting Log Sheets.

9.2 Gantt Chart




Figure 29: Detailed Gantt chart for the development lifecycle

9.3 Trello Board

Trello board screenshot placeholder

Figure 30: Kanban board on Trello

References

[1] F. P.-W. Lo, J. Qiu, Z. Wang, H. Yu, Y. Chen, G. Zhang, and B. Lo, "AI Hiring with LLMs A Context-Aware and Explainable Multi-Agent Framework for Resume Screening," arXiv2504.02870, 2025. https

[2] J. Rosenberger, L. Wolfrum, S. Weinzierl, M. Kraus, and P. Zschech, "CareerBERT Matching Resumes to ESCO Jobs in a Shared Embedding Space," *Expert Systems with Applications*, arXiv2503.02056, 2025. https

[3] H.-L. Hsu and J. Tzeng, "DAT Dynamic Alpha Tuning for Hybrid Retrieval in RAG," arXiv2503.23013, 2025. https

[4] M. Ong et al., "A Unified Approach to Routing and Cascading for LLMs," arXiv2410.10347, 2024. https

[5] Y. Du, S. Li, A. Torralba, J. B. Tenenbaum, and I. Mordatch, "Improving Factuality and Reasoning in Language Models through Multiagent Debate," *ICLR*, 2024. https

[6] Y. Liu et al., "Prompt Injection Attack against LLM-integrated Applications," arXiv2306.05499, 2023. https

[7] K. Sharma et al., "A hybrid rule-based NLP and ML approach for PII detection and anonymization in financial documents," *Scientific Reports*, doi10.1038/s41598-025-04971-9, 2025. https

[8] V. P. Ojha et al., "Whisper Finetuning on Nepali Language," arXiv2411.12587, 2024. https

[9] A. Peng, B. Nushi, E. Kıcıman, K. Inkpen, and E. Kamar, "Investigations of Performance and Bias in Human-AI Teamwork in Hiring," *AAAI*, 2022. https

[10] A. Fabris et al., "Fairness and Bias in Algorithmic Hiring a Multidisciplinary Survey," *ACM Computing Surveys*, arXiv2309.13933, 2023. https

[11] Multiple authors, "Improved intent classification based on context information using a windows-based approach," arXiv2411.06022, 2024. https

[12] P. Zhang, Z. Liu et al., "Compressing Lengthy Context With UltraGist," arXiv2405.16635, 2024. https

[13] V. Filatova, A. Zelenchuk, and D. Filatov, "AI-Driven Decision-Making System for Hiring Process," arXiv2512.20652, 2024. https

[14] Y. Liu et al., "Formalizing and Benchmarking Prompt Injection Attacks and Defenses," arXiv2310.12815, 2023. https

[15] Multiple authors, "Whisper-LM Improving ASR Models with Language Models for Low-Resource Languages," arXiv2503.23542, 2025. https

[S1] Eightfold AI, "AI Recruiting Software," 2025. https

[S2] Paradox, "Olivia Conversational AI for Recruiting," 2025. https

[S3] HireVue, "AI in Hiring," 2025. https

[S4] LinkedIn, "Recruiter 2024 Release," LinkedIn Talent Solutions, 2024. https

[S5] Soum-ik, “AI-Powered Job Portal,” GitHub, 2024. https

10 Appendices

10.1 Wireframes

insert wireframe images.



Figure 31: Candidate dashboard wireframe

10.2 Additional Diagrams

any supplementary diagrams.